

重庆 现浇框架结构模板 方涵塑料模板

产品名称	重庆 现浇框架结构模板 方涵塑料模板
公司名称	河北宏旭模具制造有限公司
价格	50.00/张
规格参数	品牌:宏旭模具 运输方式:物流 物流周期:3天
公司地址	河北省保定市莲池区东金庄乡后辛庄村
联系电话	15720001423 15720001423

产品详情

现浇框架结构模板一般用于多个边坡防护工程，生产的混凝土框架梁用于高速公路或盘山公路的边坡防护和土壤防护工程。模板的样式为方型或矩形框，选择十字交叉连接结构，运用支撑杆和螺丝进行连接，方便工人施工和操作。模具选择塑料板材加工制作，塑料应用ABS。与其他塑料材质相比，ABS材质较硬，可承受混凝土带来的压力，但使用次数较少，只能使用约200次。长期使用后，模具易破损。正常使用塑料模时，需小心轻放。使用塑料材质制作的混凝土制品表面更光滑，脱模速度更快。采用现场浇筑的方法制作，将模具放在需要使用的地方，放在中间，在模板内侧刷一层脱模剂，方便模具脱模。浇筑混凝土时，用振动棒搅拌振动，排出体内多余的气泡，使脱模后的模具表面更加光滑美观。

现浇框架结构模板的施工使用注意事项：

- 1.模板安装 在进行现浇施工前，需进行模板的安装。安装时，要严格按照设计方案和操作规程进行，保证模板的牢固和稳定。
- 2.模板拆除 在施工完成后，需进行模板的拆除。拆除时，要注意安全，使用适当工具，避免损坏模板或对边坡造成不良影响。
- 3.模板维护 在使用过程中，要定期检查和维护模板。如发现破损或变形等情况，应及时修复或更换。

Precautions for the construction and use of cast-in-place frame structure formwork:1. Before the cast-in-place construction, the installation of the template needs to be carried out. During installation, it is necessary to strictly follow the design scheme and operating procedures to ensure the firmness and stability of the template.

2. After the construction is completed, the formwork needs to be removed. When dismantling, attention should be paid to safety, appropriate tools should be used to avoid damaging the formwork or causing adverse effects on the slope.

3. Template maintenance: During use, it is necessary to regularly inspect and maintain the template. If any damage or

deformation is found, it should be repaired or replaced in a timely manner.