

四川 钢筋混凝土现浇箱涵模具 水泥箱涵模具

产品名称	四川 钢筋混凝土现浇箱涵模具 水泥箱涵模具
公司名称	河北宏旭模具制造有限公司
价格	450.00/套
规格参数	产地:河北保定 品牌:宏旭模具 加工能力:每天
公司地址	河北省保定市莲池区东金庄乡后辛庄村
联系电话	15720001423 15720001423

产品详情

钢筋混凝土现浇箱涵模具在城市基础设施建设中具有广泛的应用。无论是高速公路、轨道交通，还是商业区、居民区，只要有地下管线布局的需求，都可以看到钢筋混凝土现浇箱涵模具的身影。箱涵施工一般采用现浇，在开挖好的沟槽内设置底层，浇筑一层混凝土垫层，再将加工好的钢筋现场绑扎，支内模和外模，较大的箱涵一般先浇筑底板和侧壁的下半部分，再绑扎侧壁上部和顶板钢筋，支好内外模，浇筑侧壁上半部分和顶板。待混凝土达到设计要求的强度拆模，在箱涵两侧同时回填土。为了确保箱涵结构的质量和稳定性，施工过程中需要严格按照设计规范和标准进行施工。在施工过程中，需要使用高品质的建筑材料，并进行严格的质量检测和监控，以确保箱涵的使用寿命和安全性。在制备混凝土时，需要按照规定的配合比进行配料，并确保混凝土的质量符合要求。浇筑时，需要将混凝土均匀地注入模具中，并确保混凝土的密实度和均匀性。在浇筑过程中，还需要对模具进行振捣和抹平，以防止出现气泡和表面不平整的现象。

When preparing concrete, it is necessary to mix the ingredients according to the specified mix ratio and ensure that the quality of the concrete meets the requirements. When pouring, it is necessary to evenly inject the concrete into the mold and ensure the compactness and uniformity of the concrete. During the pouring process, it is also necessary to vibrate and level the mold to prevent the occurrence of bubbles and uneven surface.