

四川 装配式方涵模具 电力方涵模具

产品名称	四川 装配式方涵模具 电力方涵模具
公司名称	河北宏旭模具制造有限公司
价格	450.00/套
规格参数	产地:河北保定 品牌:宏旭模具 加工能力:每天
公司地址	河北省保定市莲池区东金庄乡后辛庄村
联系电话	15720001423 15720001423

产品详情

装配式方涵模具则是一种用于制作方形涵洞的模具，其形状类似于一个正方体，同样由钢板、角钢等材料制成，模具长宽高标准尺寸2米*2米*2米，模具的断面形状为八角形，两头带承插口，便于箱涵安装，更好固定，防止节间漏水。方涵施工一般采用现浇，在开挖好的沟槽内设置底层，浇筑一层混凝土垫层，再将加工好的钢筋现场绑扎，支内模和外模，较大的箱涵一般先浇筑底板和侧壁的下半部分，再绑扎侧壁上部和顶板钢筋，支好内外模，浇筑侧壁上半部分和顶板。待混凝土达到设计要求的强度拆模，在箱涵两侧同时回填土。装配式方涵模具在进行脱模作业时，需要在模具和模具之间涂上加大模具光滑度的脱模剂，脱模剂起到一定的保护罩作用，确保模具能够顺利脱模，减少时间的浪费，才能保证装配式方涵模具制作出来的成品，在工程中长期使用，保证工程的顺利进行。拆模过程中，还要注意施工安全，由专人负责指挥。在拆模作业中应注意避免导致模具局部变形或箱体棱角损坏的情况，坚决禁止出现重击或硬撬等行为。装配式方涵模具为城市的道路建设发挥了重要作用，同时美化了城市环境。 During the demolding operation of the prefabricated square culvert mold, it is necessary to apply a demolding agent that increases the smoothness of the mold between the mold and the mold. The demolding agent plays a certain protective role, ensuring that the mold can be demolded smoothly and reducing time waste, in order to ensure that the finished product produced by the prefabricated square culvert mold can be used for a long time in the project and ensure the smooth progress of the project.