

# 四川 现浇混凝土翼墙钢模具 高速公路翼墙模板

产品名称	四川 现浇混凝土翼墙钢模具 高速公路翼墙模板
公司名称	河北宏旭模具制造有限公司
价格	400.00/套
规格参数	品牌:宏旭模具 加工能力:每天 物流周期:3天
公司地址	河北省保定市莲池区东金庄乡后辛庄村
联系电话	15720001423 15720001423

## 产品详情

现浇混凝土翼墙钢模具是一种高品质、耐用、稳定的建筑模具产品，在建筑施工中起到了bukehuoque的作用。模具使用的材质为Q235材质，采用现场浇筑的方法进行制作，直接在施工的现场将模板进行安装，将两块面板拼接在一起，在模板的内侧刷上一层脱模剂，在模板的内侧放置一层钢筋网，然后进行混凝土的浇筑，等待12小时以后在对面板进行拆除，可以再混凝土的表面刷上一层反光漆，或者贴上反光条，这样即使在夜间也可以看清楚混凝土翼墙的位置。为了延长模具的使用时间，模具的外形会焊接上一层加固的钢板，以增加模板的稳定性。此外，还会在模具的外侧焊接上一层筋板，作为一层的加固，使模板更加坚固耐用，从而提高模具的使用周期。现浇混凝土翼墙钢模具的养护工作也是非常重要，这是因为整个模具在使用完成后是需要进行储存的，如果储存方式不正确的话，那么模具在后续使用的过程中就容易出现破损和老化的情况，自然生产出来的预制件也不能够很好的再去进行使用了。 Wait for 12 hours before dismantling the panel. You can apply a layer of reflective paint or stick reflective strips on the surface of the concrete, so that the position of the concrete wing wall can be clearly seen even at night. In order to extend the service life of the mold, a reinforced steel plate will be welded to the outer surface of the mold to increase its stability. In addition, a layer of rib plates will be welded on the outer side of the mold as reinforcement, making the template more sturdy and durable, thereby improving the service life of the mold.